


**5.10.11.4.1d TRANSVERSE REINFORCEMENT FOR CONFINEMENT AT PLASTIC HINGES**

The commentary for this article specifies a maximum spacing of 8" center-center of longitudinal bars.



Interlocking spirals shall be used for non-circular columns. Reinforcement details are shown in the following sketch.

